



Ref no: WBGB/S24/RO/1465/2025-26

Date: 29-12-2025

Inviting tender for the Electrical work for the renovation of KODALIA BRANCH under South 24 Parganas Region.

West Bengal Gramin Bank invites Sealed Tenders from reputed, experienced and Eligible Contractors / Agencies/ suppliers for electrical work for **KODALIA BRANCH** (PO - KODALIA, 24 PARAGANAS (S) Pin:700146) as per work schedule and specification considering the following terms & Conditions. Specifications of Works are given in **ANNEXURE –A.**

Scope of Work:

Electrical Work .

Eligibility Criteria:

4. The bidder must have prior experience in undertaking similar renovation works in Banks, Government offices or Financial Institutions.
5. Valid Trade License & GST registration Certificates are mandatory.
6. Financial soundness and capability to complete the project within stipulated timeline.

Important Dates:

4. Issue of Tender Document: 29-12-2025
5. Last Date for Submission of Tender: 05-01-2026 during Office hours.
6. Opening of Tender: 6th **January 2026** at South-24 Parganas Regional office.

Submission of Tender:

Tenders must be submitted in sealed envelopes, clearly superscribed as “**Tender for Electrical works of KODALIA BRANCH, WBGB**” and addressed to: “The Regional Manager, West Bengal Gramin Bank South 24 Parganas Regional Office, Snehadeep Apartment, Garia Station Road, Balia Kolkata-700084.

Terms & conditions:

11. The Regional Manager Reserves the right to accept or reject any or all tenders without assigning any reason.
12. The Tenderer must visit the site before submitting the tender to assess the scope of work.
13. The supplier shall be responsible for the replacement or repair of any defects discovered within 03 (Three) months of installation at their expenses.
14. Uncompromising adherence to material and workmanship quality standards is required.
15. The quotation must specify the proposed project completion time, and any deviations or delays may result in penalties against the original invoice.
16. Payment will be rendered upon satisfactory completion of the work, as outlined in the work order.
17. For any defect has been detected after installation, supplier will have to replace /repair the same on his own cost.
18. No compromise will be accepted with quality of the material and quality of work.
19. The quoter must have prior experience in undertaking similar renovations works in Bank's or Financial Institutions.
20. Valid GST Registration Certificate is mandatory.

Regional Manager

For and on behalf of
WEST BENGAL GRAMIN BANK
SOUTH 24 PGS REGIONAL OFFICE
Regional Manager

WBGB, South 24 Parganas Region.





ELECTRICAL WORKS AT KODALIA BRANCH, WBGB
ANNEXURE –A

SI No.	Description Of Item	Unit	Qnty.	Rate (Rs.)	Amount (Rs.)
1	MAIN INCOMING SFU				
	S/I/T/Commissioning of 415V, AC 50 Hz, 63 Amp. TPN Main Switch	unit	1		
2	MAIN INCOMING KITKAT				
	S/I/T/Commissioning of 415V, AC 50 Hz, 100 Amp. Kitkat	unit	4		
3	GENERATOR INCOMING CHANGEOVER				
	S/I/T/Commissioning of 415V, 63 Amp. Changeover	unit	1		
4	UPS INPUT/ OUTPUT DB				
	63 Amps/40 Amps/ 32 Amps 4P/ 2P MCB in MS enclosure box	unit	4.00		
5	DISTRIBUTION BOARDS				
a	Providing and fixing 8 way SPN double door UPS DB with incomer 1 no. 32 Amps DP MCB controlling 6 nos. 16/10 Amp SP MCB Complete.	unit	1.00		
b	Providing and fixing 4 way TPN double door AC DB for A.C. POINTS with incomer 1 no.40 Amps 4P MCB controlling 9 no. 16/10 Amp SPMCB, keeping other space as spare Complete.	unit	1.00		
6	CABLES				
a	Providing and placing in position, testing and connecting insulated PVC sheathed armoured Aluminium cable 3.5C x 25 sq. mm. to be from <u>Supply Main Switch to Kitkat</u>	r. m.	30.00		
b	Providing and laying 4 x 10 sq. mm. FR PVC coated copper conductors in pvc rigid pipe/capping-casing on surface of wall duly clamping with necessary fittings and accessories from <u>Main Switch to DB</u>	r. m.	4.00		
c	Providing and laying 2 x 6 sq. mm. & 1 x 2.5 sq. mm. FR PVC coated copper conductors in pvc rigid pipe/capping-casing on surface of wall duly clamping with necessary fittings and accessories from <u>Main DB to UPS DB and UPS IN OUT.</u>	r. m.	30.00		
d	Providing and laying 2 x 2.5 sq. mm. & 1 x 1.5 sq. mm. FR PVC coated copper conductors in pvc rigid pipe/capping-casing on surface of wall duly clamping with necessary fittings and accessories from <u>DB to SWITCH BOARDS.</u>	r. m.	350.00		
e	Providing and laying 2 x 4 Sq mm. & 1 x 1.5 sq. mm. FR PVC insulated multi stranded copper wire in suitable size pvc rigid pipe/capping-casing on surface of wall duly clamping with necessary fittings and accessories for <u>DB To AC Point and GSB.</u>	r. m.	90.00		
7	POINT WIRING				
a	Providing & fixing POINT WIRING for Ceiling and wall lights. Point wiring to be laid with 2 x 1.5 Sq. mm. PVC insulated copper conductor with all necessary accessories, such as saddles etc. on surface or embedded in wall, chasing the walls and making the surface neat afterwards. The item includes modular switch 6 AMP with all base plates & cover plates, M.S. box of same make etc.	unit	30.00		





b	Providing and fixing power point for Ceiling / Exhaust Fan points with 1 x 5 pin 6 Amp socket outlet to be provided at the location of fan	unit	15.00		
c	Providing & fixing Raw Power Point Includes 1 nos. 5 pin 5/15 AMP socket and 1 no.15 Amp switch etc. complete.	unit	10.00		
d	Providing & fixing Computer Plug Points with 3 Nos 5 pin 6 Amp sockets.1 Nos 15 amp switch, complete with all necessary accessories.	unit	11.00		
e	Providing and fixing A.C. power point wiring from AC DB	unit	4.00		
f	Providing and fixing Glow Sign Board point with timer	unit	1.00		
8	EARTHING				
a	Providing and fixing Pipe Earthing 2m. deep with 40 mm. dia. GI pipe With perforations filled with alternate layers of Charcoal and salt. The item includes Funnel on top in brick masonry chamber with CI cover for watering purpose complete.	unit	2.00		
b	Providing and fixing Copper Earth Wire 8 guage in pvc conduit in Floor / walls From earth pit to earthing station & finally connected to Main Panel Board Complete.	r. m.	60.00		
9	DATA CABLING				
a	providing and fixing IOU (information outlet unit) of AT & T make including square face plate MS housing box with RJ-45 socket etc complete	unit	8.00		
b	Providing and fixing data points with CAT-6 UTP cable from system room to individual points in 20mm PVC conduit fixed on wall, ceiling, partition etc. complete	r. m.	300.00		
c	Providing and fixing Mounting (PATCH) cords one per port.				
i	2.0 m. long	unit	8.00		
ii	1.0 m. long	unit	8.00		
10	ELECTRICAL FIXTURES				
a	Providing and Fixing Surface mounted 4' long luminaire suitable for Lamp type 18W LED (T5) or similar	unit	20.00		
b	Providing and Fixing Ceiling fans 1200 mm	unit	6.00		
c	Supplying & Fixing of exhaust fan heavy duty industrial type 225 mm sweep with 1400 RPM.	unit	3.00		
SUB TOTAL					

